

Estimate No.

IA Ref. No.

Date : 23/07/2026

Date :...../...../.....

Memo Ref. PRMS No

**Supply, Installation, Testing & Commissioning of Horizontal Multistage Submersible Fountain Pump for
Globe fountain, Near Toyota building, Wattaya**

SI No.	Description	Qty.	Rate	Amount (RO)
1	Supply, installation, testing and commissioning of one (1) no. Horizontal Multistage Stainless Steel Submersible Fountain Pump complete with 2.2 kW (3 HP), 415V, 3 Phase, 50Hz submersible motor, suitable for continuous fountain water circulation duty. Pump shall be horizontal type, IP68 protection, Class F insulation, AISI 304 stainless steel construction, stainless steel shaft, silicon carbide/carbon mechanical seal, heavy-duty sealed bearings, complete with submersible cable and all accessories required for proper operation. Approved makes: , installation of new pump, replacement of damaged gaskets, fasteners and accessories as required, electrical reconnection using waterproof joints, testing, commissioning and handing over the system in satisfactory working condition.	1 nos		
	Contractor shall verify all dimensions and existing connections before procurement. Pump performance shall match or exceed the existing fountain operating requirements and maintain existing jet height..All removed items need to be hand overed to SBG,Make site visit before quote.			
	TOTAL AMOUNT		RO.	

ANNEXURE TO SL.....

TERMS AND CONDITIONS

- 1) SCOPE OF WORK ALL AS PER SL....., **SHEET NO**..... AND **SKETCH NO**.....
- 2) COMPLETION PERIOD1..... **DAYS** INCLUDING MOBILISATION
- 3) MAINTENANCE PERIOD 2 years.FROM THE DATE OF COMPLETION AND HANDING OVER
- 4) PAYMENT **95 %** ON SATISFACTORY COMPLETION OF JOB
- 5) RETENTION **05%** OF CONTRACT VALUE FOR 12 MONTHS
- 6) PENALTY **RO.** PER DAY FOR DELAY
- 7) INSURANCE CONTRACTOR'S ALL RISK POLICY FOR **RO**..... FOR THIRD PARTY
AND PRINCIPALS EXISTING AND SURROUNDING PROPERTY IN FULL

OTHERS

- 8) MODIFICATIONS TO ANY EXISTING M & E SERVICES SUCH AS PLUMBING, ELECTRICAL, TELEPHONE AND COMPUTER ARE REQUIRED TO BE INCLUDING AND THESE SERVICE SHOULD BE PROTECTED BY THE CONTRACTOR.
- 9) MUNICIPAL APPROVAL, IF ANY INCLUDING PREPARATION AND SUBMISSION OF NECESSARY DRAWING ETC..SHOULD BE INCLUDED AND ARRANGED BY THE CONTRACTOR
- 10) ALL SERVICEABLE MATERIAL REMOVED SHOULD BE HANDED OVER TO MAINTENANCE STORE AT AL-AMARAT/WADI KABIR
- 11) CONTRACTOR TO SUBMIT SHOP DRAWINGS/MAS FOR CLIENTS APPROVAL, PRIOR TO COMMENCEMENT OF WORK.
- 12) DISPOSAL OF DEBRIS TO MUNICIPAL DUMPING YARD TO BE INCLUDED AND ARRANGED BY THE CONTRACTOR.
- 13) COLOUR AND QUALITY ETC.. OF THE MATERIAL SUBJECT TO APPROVAL FROM CLIENTS REPRESENTATIVE/ENGINEER
- 14) CONTRACTOR'S EMPLOYEES ARE ONLY ALLOWED TO WORK AT SITE. (LABOUR CARD OF THE EMPLOYEES SHOULD BE SUBMITTED FOR VERIFICATION